



PROJECT PROFILE

Large Commercial Units Huntingdon

PROJECT DESCRIPTION

Project Description

M&T Midlands Limited were successful in winning the contract to complete the major Earthworks and Groundworks elements for two brand new, commercial units in Huntingdon, Cambridgeshire.

The development project was another contract awarded by GMI Construction Group, after previously constructing a New Construction college in the middle of Birmingham.

Our works onsite commenced in April 2023 with the first phase including site clearance and cut and fill which was carried out to level off the plots in preparation for construction. Utilisation of the excavated soil enabled us to significantly reduce the waste material being removed from the site.

Once the cut and fill had been carried out, we undertook an extensive storm and foul drainage scheme including installation of three large attenuation tanks which provided an efficient and controlled storage of storm water onsite. This was followed by the foundations and external services.

As these works and the steel frame and cladding started to be erected, our focus switched to laying the int concrete office slabs, external concrete yard slabs and associated roads, car parks and pathways. The final stages of the project saw our team carry out the remaining external works and soft landscaping around the site.

Sector
Commercial

Customer
GMI Construction Group

Location
Huntingdon, Cambridgeshire

Key Facts
Groundworks
Cut and fill
Attenuation
Drainage & services
Concrete slabs
Access roads and car parking
External works & landscaping

Project Completion Date
January 2024